

# FETS Laserwire Emittance Scanner: Readiness for Linac4

*on behalf of*

*C. Gabor, A. Letchford - STFC RAL*

*J. Pozimski, P Savage – Imperial College*


*G. Boorman, A. Bosco, S. Gibson – RHUL*

*Thomas Hofmann - CERN*

*FETS Meeting, RHUL  
23/10/2013*

## Outline

- Recent progress
- Fibre coupling efficiency
- Integration with Linac4
- Laser delivery enclosure




- Since the last update, the focus has been on preparing hardware and software for Linac4 visit.

## **Main activities this month:**

- Enclosure box finished and optics + cabling installed.
- Date now agreed with Linac4 for installation at CERN:
- Gary B. will visit CERN next week (from 28<sup>th</sup> Oct) with Richard D'Arcy for BPM tests. Gary will stay on to install PXI DAQ crate for strip detector and laserwire system and check LabView software.
- Alessio, Konstantin and Stephen have agreed with Thomas to visit CERN from Wed 6 – Wed 13 November for system installation:
  - Please let us know if you would like to join.
  - We will work evenings and the weekend when particle beam is not present.
  - Aim of this visit is initial hardware set up, optic alignment, safety, DAQ, etc..
  - Expect another trip to perform test programme with beam.



# Laser and coupling box



## ■ Manlight Laser:


- Original (30 W) laser returned from France following “repair” (no modification).
- No sign of damage from transport.
- Validation tests planned before shipping to CERN

## ■ Enclosure for fibre-coupling optics


- Laser head and fibre-coupling optics will be installed in rack-mountable optical breadboard.
- Ease of installation at Linac4 racks.




# Optical fibre coupling – last time:



- Laser head and fibre-coupling mounted on optical table, within footprint of coupling box:
- 3-axis translation stage to align fibre to focus of aspheric lens.
- Initially <50% efficient due to divergent beam. With telescope > 60% coupling achieved previously....








- Coupling now improved to ~75-80%, with single lens and careful alignment.





# Beam delivery outside box



BE control





■ Camera scanned through +/- 75 mm to measure beam variation around focus.

■ Beam waist

$$w_0 = \frac{\lambda}{\pi} M^2 \frac{2f}{d}$$

■ Rayleigh length


$$z_R = \frac{\pi w_0^2}{\lambda M^2}$$

■ Beam transverse size (1/e<sup>2</sup>):

$$w(z) = w_0 \sqrt{1 + \left( \frac{z}{z_R} \right)^2}$$




# Interlocked enclosure



RHUL workshop

- Beam delivery system enclosed in aluminum box, on 450x450mm breadboard.
- The top and two side panels are removable for access.
- Opening the box breaks the interlock and dumps the laser beam.
- Key to override interlock for exceptional access / alignment.





- Position of lens defined with Linac4 CAD team. (had to increase to  $f=600\text{mm}$ )
- Beam expander and translation stage assembly moved to side of the box, to avoid the box clashing with an existing pillar at Linac4.
- Cylindrical shield from box to the Linac4 vacuum vessel.



Output beam  
to Linac4,  
with stage in  
upper range

With vertical stage in  
lowest position, mirrors  
divert light to camera


Fast photodiode

Camera on  
translation stage













- Laser and optical coupling box to be rack mounted in Linac4 tunnel, adjacent to diagnostics test bench.
- Fibre route planned: 5m length is possible.

