

FETS Laserwire Emittance Scanner – New results from CERN Linac4

on behalf of

C. Gabor, A. Letchford - STFC RAL

J. Pozimski, P. Savage – Imperial College


G. Boorman, A. Bosco, S. Gibson K. Kruchinin – RHUL

Thomas Hofmann, Federico Roncarolo - CERN

*FETS Meeting, RAL
19/03/2014*

Outline

- Summary of progress
- Linearity tests
- Bias scan
- Emittance scans
- Outlook




Main activities in past month:

- Reminder of trips so far this year:
 - First trip, 20th–22th Jan: first laserwire pulse signal, 22nd January.
 - Second trip, 10th–14th Feb: First vertical laser profile scan on 11th February.
- Late February / early March, continued data taking by CERN team.
 - Investigations of laser power linearity and response of diamond amplifiers.
 - 28th Feb, first emittance measurement with 2D laser and diamond detector scan.
 - Development of simultaneous beam current data acquisition. Increased rep rate.
- Third trip, March 2014, 10th–14th, last chance for data at 3 MeV.
 - Tests of charged and linear amplifier on diamond detector, during limited beam availability.
 - Emittance scan taken at interesting quadrupole settings.
 - Final scan yesterday, 18th March: fine emittance scan and slit scan at other quad settings. 3 MeV beam stops now... next beam at 12 MeV in ~May.


Amplified
diamond
channel

Laser PD




- Synchronous peaks in diamond detector with laser pulses.
- Residual gas background in diamond detector
- Negative / saturation effects observed – prompted addition of linear amplifier.

Slit-grid scan



Laserwire vertical scan



Konstantin Kruchinin earlier analysis


- Beam profile from traditional measurements:
 - Laser profile sigma right order of magnitude in first analysis.

Analysis by Konstantin Kruchinin


24/2/2014

Rep 1

Full Range Integration




Integration Over One Peak (10300 - 11100)




Rep 5



Full Range Integration




Integration Over One Peak (10300 - 11100)




Analysis by Konstantin Kruchinin




Laser current varied and check response
of diamond detector signal:
600V bias, 21/2/2014





- Main H⁻ beam deflected by spectrometer magnet.
- Neutral H⁰ are undeflected and arrive at a downstream 5 strip diamond detector, which can be moved into the beamline via translation stage:
 - Each horizontal strip has a vertical width of ~3.5mm.
 - Small gap of 300um between strips
 - 600V nominal bias (adjustable).
 - Initially one strip was instrumented with a charge sensitive amplifier.
 - Later a second strip was instrumented with a linear amplifier.




Analysis by Konstantin Kruchinin

Check response of diamond detector signal as bias voltage is varied:


(24/2/2014)

[Bunchers were not stable during measurement – envelope of the beam could have changed!]



Increased laser frequency


Analysis by Konstantin Kruchinin



Laser frequency increased from 30kHz to 60kHz, to double # of laser pulses per a particle pulse. Laser current increased accordingly to maintain peak height.

Laser emittance scan data taken, 28/2/2014
Diamond chl5, with charge sensitive amplifier.


File: I40228_I30212, Diamond channel 5, laser position = 28, diamond Position = -3.62, integration for segment 12, in range 11.4 - 11.7 us (second third of the segment).



Laser emittance data taken, 28/2/2014
Diamond chl5, with charge sensitive amplifier.

Analysis by Konstantin Kruchinin



Vertical diamond detector scan at each laserwire vertical position.
Integration for segment (laser pulse) I2 only:



Laser emittance data taken, 28/2/2014
Diamond chl5, with charge sensitive amplifier.

Analysis by Konstantin Kruchinin


Vertical diamond detector scan at each laserwire vertical position.
Integration for segments from 12 to 16 (left) and from 20 to 24 (right)



Laser emittance data taken, 28/2/2014

Analysis by Konstantin Kruchinin


Emittance for, diamond strip4 (scope ch11)



Laser emittance data taken, 28/2/2014

Analysis by Konstantin Kruchinin


Emittance for, diamond strip2 (scope chl2)



Laser emittance data taken, 28/2/2014


Analysis by Konstantin Kruchinin

Emittance for, diamond strip5 (scope chl3)



Analysis by
Federico Roncarolo

Laser emittance data taken, 28/2/2014
Diamond with charge sensitive amplifier, analysis of




Analysis by
Federico Roncarolo

Laser emittance data taken,
28/2/2014


Diamond with charge
sensitive amplifier, analysis of

Conventional slit + SEM grid
emittance measurement,
taken with the same
quadrupole settings:



Analysis by
Federico Roncarolo


Comparison of laser vertical scan and slid-grid profile:
First look - remarkable agreement. Analyzing emittance...
ChI2, linear amplifier, average 10th and 11th laser pulses (of 30)



- The 3 MeV run quite a success – now have lots of data to analyse!
- Scan types recorded:
 - 1D vertical laserwire scan – many!
 - 1D vertical detector scan – many!
 - 2 dimensional “emittance” scan in laserwireY and diamondY: 28/2 (shown today) and 18/3 (fine scan)
 - Laser power scan – done.
 - Beam current scan – not possible, but beam current recorded so may be able to use rising pulse shape / variations.
 - Effect of modifying quad settings – laserwire data taken at two settings (one with small vertical size and strong divergence, so limited slit-grid data).
 - 2 dimensional scan in X and Y – not a priority (not enough beam time)
- The detailed analysis now begins... aim to learn as much as we can before 12 MeV run in May / June.




2014 in detail





Schedule different from what discussed on Monday – to be now detailed by Julie


Next step: Drift Tube Linac commissioning (see presentation by S. Ramberger) – DTL1, DTL2, DTL3

February. 3 MeV measurements – **March:** moving diagnostics line, installing **DTL1** at end March – **April:** RF conditioning of DTL1 (tunnel closed, access possible during day) – **May:** Beam tests DTL1 (beam permit for May 1st!) – from **June 15th:** moving and rearranging diagnostics line, installation CCDTL and PIMS1, **DTL3** installation at end July – **August:** 1st half RF conditioning DTL3 (tunnel closed, access possible during day), 2nd half installation **DTL2** – **September:** conditioning DTL3 (2 weeks), beam measurements – **October:** beam measurements until 15.10 – **From October 15th:** installations (CCDTL last 2 modules, 100 MeV diagnostics line, transfer line) – **December:** Start HW tests 105 MeV. Windows for ion source (IS02 installation): 15.6 – 30.8 (2.5 months), 15.10 – 31.12 (2.5 months).









Fast
photodiode

Filter wheel and
camera on Z
translation stage

Port to
accelerator
vacuum chamber

Focussing lens

Beam expander on
motion stages,
X and Y

Fibre input /
services

